MUNICIPAL CORPORATION, JALANDHAR

From

Superintending Engineer (O&M),
Municipal Corporation,
Jalandhar

To

Mg. Director,
Jalandhar Heights-II,
AGI Infra Ltd, 66 Footi Road,
Pholriwal,
Jalandhar

Memo No. 400/S.E/O&M Dated 29-07-2015

Sub: **Issuance of NOC regarding disposal of sewage treated water into main Municipal Corporation Sewer nearby site of Jalandhar Heights-II, AGI Infra Ltd., 66 Footi Road, Pholriwal, Jalandhar**

Reference your application for issuance of N.O.C. regarding disposal of sewage treated water.

N.O.C. is hereby granted to the firm with the following terms and conditions:

(1) The firm is allowed to dispose the sewage treated water into the Municipal Corporation Sewer through any source nearby the site which will be treated in the Sewerage Treatment Plant installed by the Municipal Corporation at Pholriwal.

(2) The firm shall make the payment of sewerage disposal charges as per the Local Govt. norms fixed for the general public i.e. Rs. 3.80 per Kilo Litre on the domestic basis.

(3) If the rates of sewage disposal charges are revised/increased then the firm shall make the payment as per the new Notification issued by the Local Govt. at that very time.

(4) The firm is not allowed to dispose off the sewage water on the open dumps. The firm shall be held responsible for any such type of negligency.

The detail of existing capacity of sewer line at 66 Footi Road as well as STP is as under:

(i)	The designed capacity of existing main sewer of 48"(1200 mm) dia nearby the site	=	25.94 Cubic Ft. per Second or 63.55 MLD
(ii)	Present Flow of Existing Sewer	=	9.877 Cubic Feet Per Second or 24.20 MLD
(iii)	Present Flow considering Peak Factor	=	22.220 Cubic Ft. Per Sec. or 54.44 MLD
(iv)	Balance Flow Capacity Permissible	=	3.718 Cubic Ft. Per Sec. or 9.11 MLD
(v)	Flow addition from Jalandhar Heights-II	=	0.2 MLD
(vi)	The designed & commissioned capacity of existing Sewerage Treatment Plants in Jalandhar City	=	200 MLD
(vii)	Capacity likely to be commissioned shortly	=	35 MLD
(viii)	Present flow of sewerage water in the commissioned STP	=	180 MLD
(ix)	Flow permitted for future addition	=	55 MLD

(5) The firm shall install Rain Water Harvesting System and Discharge Meter on the tubewell at its own cost as per the guidelines of Hon'ble Punjab & Haryana High Court and the directions of Govt. of Punjab and the firm shall utilise only the sewage treated water or surface water sources for construction purpose.

Superintending Engineer (O&M)
Municipal Corporation
Jalandhar